Common Brick Work:- Common brick work of East outside end wall and all interior walls to resemble in appearance the common brick work on the east side of the Shipping and Testing Building adjacent, using the same kind of brick and joints.

Common Brick:- All brick to be hard burned approved Baltimore brick, arch or red, uniform color; no warped, soft or salmon brick to be used. Contractor to submit sample of brick for approval before starting work.

Face Brick Work:- The north south and west walls to be faced with face brick, same as used on the west face of the present Shipping and Testing Building adjacent. The brick size and type of joints, color of mortar and other details in general, to correspond with adjacent face brick work.

Face brick to be wetted and bonded, same as specified for common brick.

Face Brick:- Face brick to be Baltimore Brick Company dolonial or equal, samples to be summitted for approval.

Outside Tile & Plaster:- Where called for and as detailed on the architectural drawings, furnish and set tile and plaster the panels. The work in general to correspond with similar work on the west face of the Shipping and Testing Building adjacent.

Cleaning Walls:- After completion of brick and tile work, the walls are all to be thoroughly and carefully cleaned of all mortar, rubbish, discoloration, etc., both inside and out, and left in first class condition.